BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2014-15/RD/WORK_INDENT16701/CALL-2

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/11/2014-15, Date: 25.03.2015

Name of the work: Improvements to cross roads and drain in Kodigehalli village in ward no. 08.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K AMRUTRAJ	
				In Figures	In Words
1	646	Removing B.S Slab of Drain and stacking including cost of all labour, HOM of machineries etc complete as per specifications and directions of engineer in charge of the work	sqm	58.32	Rupees Fifty Eight and Thirty Two Paise Only
2	613.7	Refixing stone slabs of drains and pointing in C.M (1:3)	sqm	75.6	Rupees Seventy Five and Sixty Paise Only
3	32.3	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete. (10.0 cms thick)	sqm	704.16	Rupees Seven Hundred Four and Sixteen Paise Only
4	95	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	75.6	Rupees Seventy Five and Sixty Paise Only
5	265.2	Scarifying existing stone metal layer upto 75mm thick along with their bituminous surface, picking up scarified materials and stacking of old serviceable materials with lead of 100m, sequential spreading of the salvaged aggregates with fresh aggregates on prepared base and consolidating as per water bound macadam specifications including cost of all labour, HOM of machineries etc complete as per specifications and directions of engineer in charge of the work	Sqm	82.94	Rupees Eighty Two and Ninety Four Paise Only
6	53.04	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density etc complete as per specifications and directions of engineer in charge of the work	Cum	1438.56	Rupees One Thousand Four Hundred Thirty Eight and Fifty Six Paise Only
7	265.2	Cleaning the existing WBM road surface including removing of binding materials and other foreign matter with wire bushes and small picks, sweeping with brooms or soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	12.2	Rupees Twelve and Twenty Paise Only
8	265.2	Providing and applying primer coat for surfaces of medium porosity like cement stabilized soil base @ 1.10 Kg/Sqmt over prepared surface with S.S bitumen emulsion using bitumen tanker fitted with spray set (excluding cleaning of road surface) including cost of all material, labour HOM of machineries etc complete as per specifications and directions of engineer in charge of the work	Sqm	74.52	Rupees Seventy Four and Fifty Two Paise Only

9	702.8	Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries compelte as per specifications.	sqm	3.02	Rupees Three and Two Paise Only
10	702.8	Providing and applying tack coat using 80/100 grade bitumen (VG10) on the prepared black topped surfaces at 2.5 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all material, labour HOM of machineries complete as per specifications	sqm	18.74	Rupees Eighteen and Seventy Four Paise Only
11	26.62	KSRRB M500-18: Providing and laying semi dense bituminous concrete using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compaction as per MORTH specifications clause No. 508 complete in all respects as per specifications. using 100-120 TPH capacity H.M.P with sensor paver grading II (25-30mm) with 5% CRMB-55 grade, etc complete as per specifications and directions of engineer in charge of the work	Cum	11070	Rupees Eleven Thousand Seventy Only
12	38.00	Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface:- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications.	sqm	475.2	Rupees Four Hundred Seventy Five and Twenty Paise Only
13	76.00	Providing and constructing precast concrete solid blocks with compressive strength not less than 3.5 N/sqmm with CM 1:4 masonry with solid concrete blocks of size 40x20x20 cm conforming to IS 2185 / 1965 in superstructure including cost of all materilas, labour charges, scaffolding, curing complete as per specifications.	sqm	993.6	Rupees Nine Hundred Ninety Three and Sixty Paise Only
14	228	Providing and laying in position reinforced cement concrete M20 mix with stone aggregates 20mm and downsize for slab (including steel reinforcement) including centering and shuttering, maching mixed, concrete laid in layers not exceeding 15cm thick well compacted cost of all materials, labour, HOM of machineries, curing complete as per specifications. (Approved data rate enclosed)	sqm	1489	Rupees One Thousand Four Hundred Eighty Nine Only
15	95	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km etc complete as per specifications and directions of engineer in charge of the work	Cum	73.57	Rupees Seventy Three and Fifty Seven Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92